





**Example Project for WinQS**  
**Alterations and Additions**

Item No		Quantity	Rate	Amount
	<b>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</b>			
	<b>25MPa/19mm Strength concrete</b>			
5	Strip footings A: 6      B: 3      C: 4	m3	13	1,337.00
				17,381.00
	<b>TEST BLOCKS</b>			
6	Making and testing 150 x 150 x 150mm concrete strength test cubes A: 0      B: 0      C: 4	No	4	51.75
				207.00
	<b>CONCRETE SUNDRIES</b>			
	<b><u>Finishing top surfaces of concrete smooth with a power float</u></b>			
7	Surface beds, slabs, etc A: 0      B: 0      C: 253	m2	253	18.40
				4,655.20
	<b>ROUGH FORMWORK (DEGREE OF ACCURACY II)</b>			
	<b>Rough formwork to sides</b>			
8	Edges, risers, ends and reveals not exceeding 300mm high or wide A: 99      B: 35      C: 4	m	139	92.00
				12,788.00
	<b><u>Rough formwork to soffits</u></b>			
9	Vanity slabs, cupboards, etc A: 1      B: 0      C: 0	m2	1	220.80
				220.80
	<b>Carried to Collection</b>		R	35,252.00
	Bill No. 2 Concrete Formwork and Reinforcement <b>ACE Solutions cc</b> <b>Upgrading of Clinic Ubuntu</b>			

**Example Project for WinQS  
Alterations and Additions**

Bill No. 2

Concrete Formwork and Reinforcement

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

-2-

84,649.34

-3-

35,252.00

**Carried to Summary**

R

119,901.34

Bill No. 2

Concrete Formwork and Reinforcement

**ACE Solutions cc**

**Upgrading of Clinic Ubuntu**

**Example Project for WinQS  
Alterations and Additions**

<b>Bill No</b>	<b>FINAL SUMMARY</b>	<b>Page No</b>	<b>Amount</b>
1	Preliminaries	-1-	138,600.00
2	Concrete Formwork and Reinforcement	-4-	119,901.34
	<b>SUB TOTAL</b>		R 258,501.34
	<b>CONTINGENCY SUM</b>		
	Allow a contingency amount of R10 000,00 to be used as directed by the Principal Agent		R 10,000.00
	<b>SUB TOTAL</b>		R 268,501.34
	<b>Applicable Government Tax @ 12.5%</b>		R 33,562.67
	<b>Carried to Form of Tender</b>		R 302,064.01
	<i>ACE Solutions cc</i> <i>Upgrading of Clinic Ubuntu</i>		